

APPROVED

Date 7-21-99 *RLC*

CALHOUN COUNTY REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
CONVIS TOWNSHIP	T <u>1S</u> R <u>6W</u>	<u>D-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

27 JUL 1999 10:27:16 AM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds State of Michigan
LIBER 2147 PAGE 713

I, ROBERT R. CARR, in a field survey on JUNE 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY SYLVESTER SIBLEY D.S. IN 1826.
CALHOUN COUNTY ROAD COMMISSION WITNESS CARD, 1979, BRIDGE SPIKE IN MONUMENT BOX.
DONALD DAVIS P.S. NO. 17617, 1995, FOUND 1/2" IRON IN MONUMENT BOX ONE WITNESS APPEARS TO MATCH WITH ROAD COMMISSION 1979.

SURVEY & REMONUMENTATION

MAR 13 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BRIDGE SPIKE IN MONUMENT BOX PER CALHOUN COUNTY ROAD COMMISSION 1979.
NO OTHER EVIDENCE OF CORNER EXISTING.
REPLACE BRIDGE SPIKE WITH STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN CASTING.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN CASTING:
14" LOCUST N 35°E, 35.34' (NAIL AND SPOTTER)
11" ELM N 42°W, 53.46' (NAIL AND SPOTTER)
14" OAK S 43°E, 46.51' (NAIL AND SPOTTER)
9" MAPLE S 23°E, 34.51' (NAIL AND SPOTTER)

THIS LOCATION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Robert R. Carr*
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date 7-21-99