

1993

REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 6 9 48 AM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in
CALHOUN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R6 W G-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN ORIGINAL SURVEY OF 1826 BY LYON IN MARSH.
7" TAMARAC S 76° W 33 LINKS.
8" TAMARAC N 64° E 34 LINKS.
NO ORIGINAL WITNESSES REMAIN. ROAD CONSTRUCTION NOW ACROSS AREA.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE AS CALLED FOR IN ACT 74 OF 1987, IN LIBER 1427, ON PAGE 383, AND AS USED BY DE KEYSER IN 1977.
ACCEPTED THIS CORNER AS IT HAS BEEN USED IN MANY SURVEYS OF THIS AREA.
LOCATION AGREES WITH OCCUPATIONS IN AREA.

LIBER 1427 PAGE 281

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERTSEN MONUMENT WITH BRASS CAP IN MONUMENT BOX.
NAIL & TAG RR TIE POST N 48° E 40.15'.
NAIL & TAG RR TIE POST N 50° W 46.10'.
NAIL & TAG TWIN 16" MAPLE N 35° E 65.42'.
NAIL & TAG 14" MAPLE N 65° E 76.79'.
2.3' NORTH OF CENTERLINE OF "N" DRIVE NORTH.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date SEPTEMBER 10, 1993