

1993

REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 6 9 48 AM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in
CALHOUN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 6 W G-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN ORIGINAL SURVEY OF 1825 BY LYON.
NO ORIGINAL WITNESSES REMAIN.
12" WHITE OAK N 61° E 16 LINKS.
14" OAK N 69° W 10 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON FROM WITNESSES OF CORBIT M.D.S.H. OF 1966.
5/8" IRON OVER PIPE WITH ROCKS AROUND.
WITNESSES CHECK AND DISTANCE TO MARSHALL CORNER GOOD.
ACCEPTED THIS CORNER AS A PERPETUATION OF ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LIBER 1707 PAGE 280

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT WITH BRASS CAP IN MONUMENT BOX.
NAIL & TAG UTILITY POLE N 15° E 60.92'.
NAIL & TAG TWIN 18" CHERRY N 65° E 72.65'.
FACE GAS LINE MARKER S 60° E 49.80'.
NAIL & TAG UTILITY POLE S 15° E 122.05'.



Signed by Donald J. Davis

Date SEPTEMBER 13, 1993.

Surveyor's Michigan License No. 17617