

1993

RECORDED

COMMISSION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 6 9 47 AM 93

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. NORLANDER

For corners in

CALHOUN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 6 W H-11
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN ORIGINAL SURVEY OF 1826 BY LYON.  
14" WHITE OAK N 04° E 21 LINKS.  
28" WHITE OAK N 68° W 31 LINKS.  
ALL WITNESSES GONE.  
12" STONE AND BRICK SET IN 1898.  
1" IRON SET BY A.H. CHASE IN 1942.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON WITH ROCKS FROM COUNTY ROAD COMMISSION PLAN AND DESCRIPTIONS.  
8" LOCUST N 50° E 11.5'.  
6" LOCUST N 85° E 19.4'.  
10" ELM S 60° W 46.4'.  
IRON ACCEPTED AS THE LOCATION OF THE CORNER BY LOCAL USE AND HAS BEEN USED FOR SURVEYS IN THE AREA.  
1/2" IRON 9.70 FEET EAST RECORDED AS SOUTH 1/4 POST IN 1977 IN LIBER 1158, ON PAGE 905.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNISEN MONUMENT WITH BRASS CAP WITH ROCKS AROUND.  
NAIL & TAG 8" LOCUST N 50° E 11.53'.  
NAIL & TAG 6" LOCUST N 85° E 19.55'.  
NAIL & TAG R.R. TIE POST EAST 20.85'.  
12" ELM S 60° W 46.42'.  
6.5' EAST OF FENCE SOUTH.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

LIBER 1707 PAGE 271



Signed by Donald J. Davis

Date SEPTEMBER 15, 1993

Surveyor's Michigan License No. 17617