

1993

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

OCT 6 - 9 48 AM '93

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. NORLANDER

For corners in  
CALHOUN

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 1 S R 6 W H-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN ORIGINAL SURVEY OF 1826 BY LYON. PINK ROCK FOUND BY CORBIT (M.D.S.H.) IN 1966.  
CORBIT SET 1" PIPE.  
16" PINE S 67° W 73.48'.  
17" PINE S 42° W 37.49'.  
29" CHERRY N 01° E 30.77'.  
CORNER RECORDED BY GARR IN 1990 IN LIBER 1525, PAGE 534.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE IN MONUMENT BOX FROM WITNESSES AND CORNER CHECKED WITH WITNESSES ABOVE.  
ACCEPTED THIS CORNER AS A TRUE PERPETUATION OF THE ORIGINAL CORNER. IT HAS BEEN USED IN THIS AREA FOR MANY YEARS.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

LIBER 1707 PAGE 282

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT WITH BRASS CAP IN MONUMENT BOX.  
NAIL & TAG 24" PINE S 42° W 37.32'.  
NAIL & TAG 20" PINE S 67° W 72.35'.  
NAIL & TAG TWIN 16" CHERRY N 65° W 67.85'.  
NAIL & TAG TWIN 28" CHERRY N 01° E 30.39'.  
NAIL & TAG 36" MAPLE S 45° E 56.57'.



Signed by Donald J. Davis Date SEPTEMBER 13, 1993

Surveyor's Michigan License No. 17617