

APPROVED
 at 7-27-94 DJD
 CALHOUN COUNTY
 REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

For corners in
Calhoun
 (County)

Located In: Corner Code #

- | | | | | | | | |
|---------------------------------------|---|---|---|---|---|---|------|
| 1. Public Land Survey | T | 1 | S | R | 6 | W | I-11 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling
in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous
Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

28 JUL 94 11:13 A.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Donald J. Davis, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--------------------------------|---------------------------------------|
| 1825 Lyon | M.D.S.H. Records. |
| Set Post | 3/4" Gas pipe centerline 16 Mile Road |
| 28" White Oak S 18° W 42 Links | Utility Pole N 51° W 22.16' |
| 10" White Oak N 9° W 52 Links | Utility pole N 52° E 25.29' |
| | 38" Hickory S 86° W 23.85' |

SURVEY &
 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in centerline of road. Found recent spotter nails in trees
 Corner used in area surveys.
 Accepted as good local perpetuation of corner.

OCT 24 1994

COMMISSION

LIBER 1760 PAGE 637

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Berntsen monument and monument box.
- Nail in 14" Hickory West 24.00'
- Nail in 12" Pine East 18.90'
- Nail in 30" Hickory S 30° W, 38.90'
- NW corner of brick planter S 20° E 99.20'



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date July 25, 1994