

1993

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

OCT 6 9 48 AM 93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in
CALHOUN

(County)

Located In:

Corner Code --#

- 1. Public Land Survey T 1 S R 6 W I-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN ORIGINAL SURVEY OF 1825 BY MULLETT.

16" WHITE OAK N 86° E 237 LINKS. }
12" BURR OAK N 26° W 229 LINKS. } ALL GONE.

CORNER USED FOR CONSTRUCTION OF HIGHWAY I-69 AND SURVEYS IN AREA.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE AND ROCKS AT INTERSECTION OF OLD ROADS.

PIPE ACCEPTED AS LOCATION OF CORNER THROUGH LOCAL USE AND PERPETUATION.

LIBER 1707 PAGE 279

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET HARRISON CAST IRON MONUMENT IN OLD ROAD BED (ROAD RELOCATED).

- NAIL & TAG 18" HICKORY S 50° W 43.50'.
- NAIL & TAG 24" OAK N 30° E 60.76'.
- NAIL & TAG 16" WALNUT N 50° W 53.36'.
- NAIL & TAG 36" OAK S 60° E 63.50'.



Signed by Donald J. Davis

Date SEPTEMBER 13, 1993

Surveyor's Michigan License No. 17617