

APPROVED

ate 7-27-94
CALHOUN COUNTY
EMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

28 JUL 94 11:13 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> S R <u>6</u> W	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on June 22, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825, Lyon	M.D.S.H., 1966, Corbit 3/4" pipe 48" long
Section corner in lake.	10" Cherry N 25" W 13.80'
	21" Cherry S 80° W 12.93'
	24" Cherry S 30° E 33.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe, 48" long & witnesses or remains of witnesses form Corbit of M.D.S.H.
Accepted as good location of corner.

SURVEY &
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1760 PAGE 638

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument & carsonite marker.

8" Maple West 7.0'

14" Maple S 10° W 16.2'

12" Maple S 30° E 18.9'

26" Cherry N 5° W 21.0'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date July 25, 1994