

WAR 30 1999

APPROVED

Date 12-9-98 REC CALHOUN COUNTY REMONUMENTATION
CALHOUN COUNTY LAND CORNER RECORDATION CERTIFICATE
REMONUMENTATION Filing Requirement of Act 74, Mich. P.A. 1970

SECTION STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

15 DEC 1998 3:41:32 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2087 PAGE 948

Register of Deeds Stamp & File Number

CALHOUN (County)	Located In:	Corner Code #
CONVIS TOWNSHIP		
1. Public Land Survey	T <u>1S</u> R <u>6W</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on DECEMBER 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 1 & 2

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY, D.S. 1826

P.A. COURTRIGHT, COUNTY SURVEYOR 1904, FOUND A STONE AND CROCKERY IN CENTER OF ROAD, IN LINE WITH FENCE EAST.

STATE HIGHWAY DEPT. 1966, SET OLD PICK IN ROAD FROM OLD WITNESSES (23" HICKORY FROM STATE HIGHWAY DEPT. MATCHES 8" HICKORY FROM P.A. COURTRIGHT)

CONSUMER POWER SURVEY, 1966 FOUND OLD PICK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE MATCHING ONE WITNESS REMAINING FROM CONSUMER POWER SURVEY, AREA WAS EXCAVATED WITH I-69 CONSTRUCTION.

REPLACED 1" PIPE WITH BERNTSEN MONUMENT WITH CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MOUMENT WITH CARSONITE WITNESS POST ON EAST SIDE.

- 8" PINE, N26°E 73.29' (SET SPOTTER)
- 28" OAK, S85°E 25.49' (SET SPOTTER)
- 4" HICKORY, S33°W 76.94' (SET SPOTTER)
- ANGLE IRON CORNER POST, N61°E 60.75'
- 40' ± EASTERLY OF CENTERLINE OF ROAD.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	0	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date DECEMBER 9, 1998