

SURVEY &
REMONUMENTATION

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 18 2 21 PM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in

CALHOUN (County)	Located In:	Corner Code #
PENNFIELD		
1. Public Land Survey	T 1S R 7W	A-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on SEPTEMBER 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A-9 RESURVEY	ARNDTS 1927
TILE 48 LINKS SOUTH OF PENNFIELD CORNER.	2" IRON
SUGAR MAPLE 14" N41°E, 51 LINKS	28" MAPLE N49°E, 33.9 FT.
WHITE OAK 16" S48°E 46 LINKS	15" HICKORY S22°W, 73.4 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 FOUND 1-1/2 PIPE IN MONUMENT BOX OVER TILE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 RE-PLACED PIPE AND TILE WITH STANDARD CALHOUN COUNTY REMON MONUMENT WITH BRONZE CAP AND RAISED MONUMENT BOX TO SURFACE.
NAIL AND SPOTTER IN SOUTH SIDE OF U-POLE, S78°E, 25.12 FT.
NAIL AND SPOTTER IN SOUTH SIDE OF U-POLE, S25°E, 49.90 FT.
CENTER OF 12" MAPLE S80°W, 58.0 FT.
BEDFORD CORNER NORTH 31.19 FT.
FACE OF FENCE POST S62°E, 44.66 FT.



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date NOV. 15, 1993

LIBER 1716 PAGE 444