

**SURVEY &
REMONUMENTATION**

APR 26 1995

APPROVED
to 11-28-94
**CALHOUN COUNTY
REMONUMENTATION.**
of corners in

COMMISSION
**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TWP	T 1 S R 7 W	A-11
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED
29 NOV 94 10:23 A.M.
ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

ROBERT R. CARR, in a field survey on NOVEMBER 22, 19 94, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Description of original monument and accessories and/or subsequent restoration:
ORIGINAL CORNER SET BY DEPUTY SURVEYOR JOHN MULLETT 1925.
RE-SURVEY CORNER SET BY COUNTY SURVEYOR J.M. GIFFORD 1891.
FOUND CORNER 42 LINKS SOUTH OF BEDFORD CORNER
SET STAKE (TILE).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 3" X 12" SOLID TILE IN MONUMENT BOX
27.78 FEET SOUTH OF BEDFORD CORNER.
REMOVED TILE AND PLACED BERNTSEN MONUMENT IN MONUMENT BOX.

LIBER 1778 PAGE 568

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
BERNTSEN MONUMENT IN MONUMENT BOX
SW CORNER OF SAND STONE FACE OF STORE BUILDING N71°E 74.27 FEET.
NE CORNER HOUSE FOUNDATION S60°W 86.52 FEET
NW CORNER HOUSE FOUNDATION S53°E 83.37 FEET.
NAIL & SPOTTER IN NE SIDE OF U-POLE N23°W 53.25 FEET.



Witnessed by Robert R. Carr Date NOVEMBER 22, 1994
Surveyor's Michigan License No. 20704