

1993

COMMISSION

CALHOUN COUNTY

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE S. NORLANDER

SEP 1 10 33 AM '93

RECORDED

For corners in  
CALHOUN

(County)

Located In:

Corner Code #

- |                                       |                         |            |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey                 | T <u>1S</u> R <u>7W</u> | <u>B-9</u> |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                         |            |
| 5. Private Claims _____               |                         |            |

Register of Deeds Stamp & File Number

DONALD J. DAVIS, in a field survey on JULY 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY OF 1891.

HARRISON MONUMENT PLACED AT CORNER DURING PLATTING OF CARRIAGE HILLS DEVELOPMENT.

12" HICKORY S 31° W 84 LINKS. (OLD) GONE.

16" YELLOW OAK N 87° W 21 LINKS (OLD) GONE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND HARRISON MONUMENT AT LOCATION FROM PLAT OF CARRIAGE HILLS, LIBER 18, PAGE 30A.

ACCEPTED THIS MONUMENT AS A TRUE PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

HARRISON MONUMENT WITH ROCKS AROUND.

14" CHERRY N 70° E 31.25' NAIL.

UTILITY POLE S 50° W 86.85' NAIL.

12" OAK S 30° E 57.25' NAIL.

CONSUMERS POWER CO. MARKER N 30° W 2.41'.



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date August 13, 1993