

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN

(County)

Located In:

Corner Code #/

1. Public Land Survey	T 1 S R 7 W	B-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SEP 1 10 32 AM '93
CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

I, DONALD J. DAVIS, in a field survey on JULY 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY OF 1891, BY GIFFORD.
5" HICKORY S 15½° W 13 LINKS.
4" WHITE OAK S 87° W 72 LINKS.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BROKEN CONCRETE MONUMENT WITH PIECES OF TILE AROUND.

THIS CORNER IS ACCEPTED AS A TRUE PERPETUATION OF THE ORIGINAL SURVEY CORNER.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED CONCRETE MONUMENT WITH BERSTEN STAINLESS STEEL MONUMENT WITH BRONZE CAP.
16" OAK S 78° E 49.10' NAIL & SPOTTER.
12" OAK N 86° E 51.07' NAIL & SPOTTER.
24" HICKORY EAST 73.73' NAIL & SPOTTER.
UTILITY POLE S 80° W 71.13' NAIL & SPOTTER.
3.5' EAST OF EASTERLY POWER LINE OVERHEAD.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 12, 1993