

SURVEY & REMONUMENTATION

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN

(County)

Located In:

Corner Code #

Public Land Survey	T <u>1</u> S R <u>7</u> W	B-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANN F. B. NORLANDER
SEP 1 10 33 AM '93

RECORDED

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

DONALD J. DAVIS, in a field survey on JULY 28, 1993,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY IN 1891.

CONCRETE MONUMENT SET FOR PLAT OF BELLA VISTA ESTATES NO. 1, LIBER 11, PAGE 50.

9" YELLOW OAK N 89½° E 25 LINKS (OLD) GONE.

7" HICKORY S 79° W 56½ LINKS (OLD) GONE.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE PLAT MONUMENT 33 INCHES DEEP UNDER FILL, CHECKED DISTANCE TO OTHER PLAT MONUMENTS.

THIS CORNER IS ACCEPTED AS A TRUE PERPETUATION OF THE ORIGINAL SURVEY CORNER.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNSTEN STAINLESS STEEL MONUMENT WITH BRONZE CAP OVER CONCRETE MONUMENT.

UTILITY POLE S 85° E 56.77' NAIL & SPOTTER

SE CORNER BRICK HOUSE N 35° E 24.55'.

SW CORNER BRICK HOUSE N 55° W 38.92'.

NE CORNER BRICK HOUSE S 12° E 53.50'.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 12, 1993