

APPROVED

Date 11/25/97 ERC

**CALHOUN COUNTY
REMONUMENTATION**

For corners in

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

1 DEC 97 4:49 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1980 PAGE 503

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TOWNSHIP	T <u>1S</u> R <u>7W</u>	<u>E-1</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT R. CARR, in a field survey on APRIL 24, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 SYLVESTER SIBLEY D.S.; W.O. 8" S35°W 35 LKS; W.O. 7" S44°E 63 LKS.
 1891 J.M. GIFFORD, RESURVEY; SET POST FROM ONE U.S. BEARING; W.O. 24" S47°W 87 LKS.
 1965 CONSUMER POWER COMPANY SURVEY, SET IRON FROM OLD WITNESSES TAKEN WHEN
 PIECES OF TILE WERE FOUND AND MOVED NORTH TO BE ON BASE LINE, 5 WITNESSES.
 1965 DAVIS, SAME WITNESSES AS C.P.CO. SURVEY.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON FROM THREE OF C.P.CO. WITNESSES.
 ACCEPTED LOCATION AS TRUE PERPETUATION OF CORNER AND
 SET BERNTSEN MONUMENT WITH CARSONITE WITNESS POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT
 CARSONITE WITNESS POST, NW 1.0 FEET
 SET SPOTTER IN CLUMP OF 8 BASSWOOD (6" TO 12"), S40°W 32.19 FEET
 SET SPOTTER IN 10" OAK, N68°W 45.31 FEET
 SET SPOTTER IN 30" CHERRY, N02°E 55.58 FEET
 SE CORNER OF POLE BARN, N48°W, 78.02 FEET.

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

Date 11/24/97

Signed by [Signature]
 Surveyor's Michigan License No. 20704

