

**APPROVED**

Date 11/25/97 ERC  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

For corners in

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

1 DEC 97 4:49 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1980 PAGE 500

Register of Deeds Stamp & File Number

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
PENNFIELD TOWNSHIP		
1. Public Land Survey	T <u>1S</u> R <u>7W</u>	<u>E-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on APRIL 22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826 SYLVESTER SIBLEY D.S.; W.O. 30" S79"W 16 LKS; W.O. 28" S62"E 36 LKS.  
1891 J.M. GIFFORD; FOUND STONE SET BY S. PRATT AND SET TILE  
Y.O. 24" WEST 19 LKS; Y.O. 20" S45"E 37 LKS.  
1948 C.F. CHAMBERS; TILE, 5 WITNESSES  
1965 CHASE, DEKEYSER & ALDEN, 3/4" IRON PIPE OVER TILE, 3 WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE OVER BROKEN TILE, THREE CHAMBERS AND TWO CHASE, DEKEYSER & ALDEN WITNESSES STANDING.  
ACCEPTED AS TRUE PERPETUATION OF CORNER AND REPLCED 3/4" IRON PIPE WITH BERNTSEN MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX  
SOUTHEAST CORNER OF HOUSE FOUNDATION, N44"W 121.22 FEET  
NORTHEAST CORNER OF 36"x18" CONCRETE PILLAR, N87"W 25.43 FEET  
SET SPOTTER IN TWIN 10" CHERRY, S35"W 65.02 FEET  
SET SPOTTER IN 20" CHERRY, S84"E 22.35 FEET  
SET SPOTTER IN 12" MAPLE, N46"E 28.16 FEET.

**SURVEY & REMONUMENTATION**

APR 07 1998

SECTION \_\_\_\_\_

Date 11/24/97

Signed by [Signature]  
Surveyor's Michigan License No. 20704

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

