

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept. 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

Calhoun

Located In:

Corner Code #

Pennfield Twp.
(County)

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>1</u> S R <u>7</u> W | <u>E-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:00 A.M.

Register of Deeds Stamp File Number
CLERK - REGISTER OF DEEDS

I, Donald J. Davis, in a field survey on August 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Sibley. Resurvey in 1897 by Whitney, tile set.
Tile found by Davis in 1976. Iron set beside. No witnesses near.
Tile used for surveys in Sections 29 and 30.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile and iron.

Accepted as good perpetuation of corner point.

CORNER
REMONUMENTATION

LIBER 1822 PAGE 26

FEB 22 1996
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument and marked with carsonite marker.
No witnesses near.
Corner located S 89°-57'-00" E 5304.78 feet from West 1/4 Post and S 00°-46'-15" W 2648.62 feet from northeast corner of section. Bearings based on plat of Driscoll Estates in Southwest 1/4 of Section 29.
Corner is 2670 feet East of Capital Avenue N.E.

Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date September 19, 1995

