

APPROVED

Date 11/25/97 RRC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

1 DEC 97 4:48 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1980** PAGE **498**

Register of Deeds Stamp & File Number

For corners in _____

CALHOUN Located in: _____ Corner Code # _____
(County)

PENNFIELD TOWNSHIP

1. Public Land Survey T 1S R 7W G-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ROBERT R. CARR, in a field survey on APRIL 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 SYLVESTER SIBLEY D.S. W. OAK 7" S73-1/2°E 125 LKS.
- 1891 GIFFORD RESURVEY, RAN BASELINE AND SECTION LINE FROM SOUTH AND SET POST AT INTERSECTION, ELM 14" N34°E 63LKS.
- 1930 TILE, 4 WITNESSES, NO NAME
- NO DATE, SLEIGH SHOE 6 WITNESSES
- NO DATE, J. ALDEN, 3 WITNESSES
- 1964 D. HOOTH, MICHIGAN STATE HIGHWAY DEPARTMENT
- FOUND 1" PIPE, 4 WITNESSES
- 1965 CONSUMER POWER COMPANY SURVEY, FOUND P.K. NAIL OVER 3/4" PIPE
- SAME WITNESSES AT M.S.H.D.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MONUMENT BOX MATCHING LOCATION INDICATED ON CONSUMER POWER COMPANY SURVEY OF 1965. DISTANCES TO SOUTH 1/4 POST, SECTION 34 AND SOUTHWEST CORNER, SECTION 34, ASSYRIA TOWNSHIP CHECK. ACCEPTED AS BEST EVIDENCE OF CORNER AND REPLACED 1/2" IRON WITH BERNTSEN MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX
SET SPOTTER IN UTILITY POLE, S29°W 200.86 FEET
SET SPOTTER IN UTILITY POLE, N78°W, 204.83 FEET
SET SPOTTER IN UTILITY POLE, N05°W, 228.05 FEET
SET SPOTTER IN UTILITY POLE, S70°E, 225.07 FEET
ON WEST EDGE OF SOUTH BOUND LANE OF HIGHWAY M-66
ON CENTERLINE, MORE OR LESS, OF BASELINE ROAD.

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 20704

Date 11/24/97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	
13													

