

MAR 30 1999

APPROVED

Date 11-18-98 RRC
**CALHOUN COUNTY
REMONUMENTATION.**

SECTION
**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 1998 3:30:58 PM

For corners in

COUNTY <small>(County)</small>	Located In:	Corner Code #
PENNFIELD TOWNSHIP	T ___ R ___	_____
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>3</u> T <u>1S</u> R <u>7W</u>	<u>H-1</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2079** PAGE **913**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTH 1/4 POST OF SECTION 3

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET WITH ORIGINAL GOVERNMENT SURVEY.
JON DAVIS, M.S.H.D. 1964, FOUND FLOW POINT AND RAISED WITH 2" PIPE.
CONSUMER POWER COMPANY, 1966, 2" PIPE.
R.R. CARR, P.S. #20704, 1990, FOUND 1/2" IRON MATCHING 1964 STATE HIGHWAY WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN 2" PIPE OVER FLOW POINT IN MONUMENT BOX.
RAN BASELINE FROM SOUTH 1/4 POST OF SECTION 34, TOWN 1 NORTH, RANGE 7 WEST, TO SOUTHEAST CORNER OF SECTION 34 AND FOUND FLOW POINT TO BE ON LINE.
REMOVED 1/2" IRON AND 2" PIPE AND PLACED BERNTSEN MONUMENT OVER PLOW POINT IN EXISTING MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX
8" OAK, S14° E 26.73 FEET (NAIL AND SPOTTER)
10" MAPLE, N50°E 33.34 FEET (NAIL AND SPOTTER)
TWIN 20" HICKORY, N30°W 32.85 FEET (NAIL AND SPOTTER)
40" OAK, S72°W 63.03 FEET (NAIL AND SPOTTER)
1'± SOUTH OF CENTERLINE OF EAST & WEST ROAD.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS.
THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOVEMBER 16, 1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

