

MAR 30 1999

APPROVED

Date 9-16-98 RLL
CALHOUN COUNTY
REMONUMENTATION.

SECTION
CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

25 SEP 1998 2:27:47 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2062 PAGE 583

Register of Deeds Stamp & File Number

CALHOUN	Located In:	Corner Code #
(County)		
PENNFIELD TOWNSHIP		
1. Public Land Survey	T <u>1S</u> R <u>7W</u>	<u>1-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on AUGUST 21, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 2 AND 3

A. Description of original monument and accessories and/or subsequent restoration:

SYLVESTER SIBLEY D.S. 1826 SET ORIGINAL CORNER
J.M. GIFFORD 1891, FOUND STUMP OF ONE GOVERNMENT BEARING AND STAKE SET BY PRATT, SET POST (TILE)
D. DAVIS, 1965, TILE AND ROCKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SOLID TILE IN ROCKS NEXT TO NORTH SIDE OF FENCE CORNER POST, DUG AND FOUND PIECES OF BROKEN TILE 2 FEET, MORE OR LESS, DEEP.

REPLACED TILE WITH BERNTSEN REMONUMENTATION MONUMENT AND TOOK NEW WITNESSES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704
14" OAK, S60°E 12.39 FEET, SET SPOTTER
28" OAK, N15°E 25.81 FEET, SET SPOTTER
10" MAPLE, S40°W 29.88 FEET, SET SPOTTER
5" MAPLE, N55°E 16.20 FEET, SET SPOTTER
28" MAPLE, N87°E 78.35 FEET, SET SPOTTER
FENCES NORTH, SOUTH, EAST AND WEST.

THIS IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3	2			1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by [Signature]

Date SEPTEMBER 16, 1998

Surveyor's Michigan License No. ROBERT R. CARR 20704