

MAR 30 1999

APPROVED

Date 11-18-98 KRC
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 1998 3:30:46 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2079** PAGE **912**

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TOWNSHIP	T <u>1S</u> R <u>7W</u>	<u>K-1</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTHEAST CORNER OF SECTION 2, NORTHWEST CORNER OF SECTION 1
A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY D.S. 1826.
J.M. GIFFORD, RESURVEY, 1891, SET TILE FROM REMAINS
OF ONE U.S. BEARING TREE.
D. DAVIS, 1965, 3/4" PIPE AND WITNESSES.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE 5 FEET NORTH OF EAST-WEST FENCE PER DAVIS 1965.
RAN BASE LINE FROM SOUTHWEST CORNER OF SECTION 36, TOWN 1 NORTH,
RANGE 7 WEST, TO SOUTH 1/4 POST OF SECTION 36 AND FOUND 3/4" PIPE
TO BE 6.0 FEET NORTH OF BASE LINE. DUG EXTENSIVELY FOR TILE, BUT COULD
NOT FIND. HELD EAST-WEST LOCATION OF 3/4" PIPE AND SET
BERNTSEN MONUMENT 6.0 FEET SOUTH ON BASELINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT WITH CARSONITE WITNESS POST BESIDE.
0.50 FEET SOUTH OF FENCE LINE EAST & WEST
12" MAPLE, N72°W 29.72 FEET (NAIL AND SPOTTER)
10" MAPLE, N02°W 10.62 FEET (NAIL AND SPOTTER)
12" MAPLE, N68°E 19.90 FEET (NAIL AND SPOTTER)
14" MAPLE, N82°E 39.29 FEET (NAIL AND SPOTTER).

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOVEMBER 16, 1998