

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN

Located In:

Corner Code #/

Public Land Survey

T 1S R 7W

K-9

Property Controlling
in Section

Miscellaneous
Property in Sec.

S T R
S T R
S T R
S T R

Lot No. _____, Recorded Plat _____
Private Claims _____

DONALD J. DAVIS, in a field survey on JULY 22, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY OF 1891.
NO RESURVEY WITNESSES REMAIN.
12" WHITE OAK N 88½° W 22 LINKS.
12" HICKORY N 43° E 22 LINKS.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 6" PIECE OF SOLID TILE 2 FEET UNDER FROM WITNESSES.
14" R. OAK WEST 31.29
24" OAK N 4° W 22.6'
2' NORTH OF OLD E & W FENCE.
3' EAST OF OLD FENCE NORTH.

THIS CORNER IS ACCEPTED AS A TRUE PERPETUATION OF THE ORIGINAL CORNER.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED BERNSTEN STAINLESS STEEL MONUMENT WITH BRONZE CAP AT POINT.
TWIN 14" R. OAK N 70° E 8.87' P.K. NAIL
24" W. OAK N 30° W 22.60' P.K. NAIL
18" HICKORY WEST 31.29' P.K. NAIL
TRIPLE 24" R. OAK N 4° W 35.02 P.K. NAIL

CLERK-REGISTER
CALHOUN COUNTY MICHIGAN
ANN ARBOR, MICHIGAN
SEP 1 10 33 AM '93

RECORDED

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 2-13. A dot is located at the intersection of column K and row 9.

Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date Sept. 13, 1993

