

MAR 30 1999

APPROVED

Date 9-16-98 RRC
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 SEP 1998 2:28:21 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2062 PAGE 586

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TOWNSHIP	<u>T 1S R 7W</u>	<u>M-2</u>
1. Public Land Survey	<u>T</u> <u>R</u>	<u> </u>
	<u>T</u> <u>R</u>	<u> </u>
	<u>T</u> <u>R</u>	<u> </u>
2. Property Controlling in Section	<u>S</u> <u>T</u> <u>R</u>	<u> </u>
	<u>S</u> <u>T</u> <u>R</u>	<u> </u>
3. Miscellaneous Property in Sec.	<u>S</u> <u>T</u> <u>R</u>	<u> </u>
	<u>S</u> <u>T</u> <u>R</u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, ROBERT R. CARR, in a field survey on AUGUST 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

EAST 1/4 POST OF SECTION 1

A. Description of original monument and accessories and/or subsequent restoration:

SYLVESTER SIBLEY D.S. 1826 SET ORIGINAL CORNER
J.M. GIFFORD 1891 RESURVEY, OBLITERATED, ESTABLISHED BY MEASURING FROM
THE 1/4 LINE IN CONVIS TOWNSHIP, SET POST (TILE)
D. DAVIS 1965, 1" SOLID IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DAVIS 1" IRON WITH STUMP OF WITNESS REMAINING.

1/4 LINE FENCE RUNNING EAST IN SECTION 6, CONVIS TOWNSHIP IS 102.3 FEET SOUTH IN AGREEMENT WITH G.L.O. PLAT MAP, THIS WOULD INDICATE THAT DAVIS IRON IS AT LOCATION ESTABLISHED BY GIFFORD.

DUG EXTENSIVELY BUT FOUND NO REMAINS OF TILE.

PLACED BERNTSEN REMONUMENTATION MONUMENT OVER 1" IRON, CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704
8" CHERRY, S80°E 36.75 FEET, SET SPOTTER
8" ASH, N49°W 53.12 FEET, SET SPOTTER
11" WALNUT, N53°E 35.36 FEET, SET SPOTTER
CENTERLINE OF NORTH AND SOUTH ROAD IS WEST 111 FEET, MORE OR LESS.
1/2" IRON, WEST 78.06 FEET.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998