

MAR 30 1999

APPROVED

Date 9-16-98 RCC
CALHOUN COUNTY
REMONUMENTATION.

SECTION
CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

25 SEP 1998 2:28:10 PM

| | | |
|------------------------------------|-------------------------|---------------|
| <u>CALHOUN</u> | Located in: | Corner Code # |
| (County) | | |
| PENNFIELD TOWNSHIP | | |
| 1. Public Land Survey | T <u>1S</u> R <u>7W</u> | <u>M-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2062** PAGE **585**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on AUGUST 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|---|----|---|----|---|----|---|---|----|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | | 4 | | 3 | | 2 | | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | | 9 | | 10 | | 11 | | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | | 16 | | 15 | | 14 | | | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | | 21 | | 22 | | 23 | | | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | | 28 | | 27 | | 26 | | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | | 33 | | 34 | | 35 | | | 36 |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

EAST 1/4 POST OF SECTION 12

A. Description of original monument and accessories and/or subsequent restoration:

SYLVESTER SIBLEY D.S. 1826 SET ORIGINAL CORNER
J.M. GIFFORD 1891 RESURVEY, FOUND BOTH GOVERNMENT BEARING TREES
AND USED SAME FOR WITNESSES TO NEW CORNER POST (TILE)
A.H. CHASE 1935, CONCRETE MONUMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A.H. CHASE CONCRETE MONUMENT WITH STUMP OF ONE WITNESS BY CHASE 1935 REMAINING.

REPLACED CONCRETE MONUMENT WITH BERNTSEN REMONUMENTATION MONUMENT
WITH BROKEN CONCRETE MONUMENT AROUND IT AND CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704
10" ASH, S36°W 16.74 FEET, SET SPOTTER
11" MAPLE, S18°E 36.66 FEET, SET SPOTTER
22" OAK, N03°W 51.68 FEET, SET SPOTTER
18" ASH, N57°E 50.86 FEET, SET SPOTTER
CORNER IS IN LOW WOODED MARSH.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998