

MAR 30 1999

# APPROVED

Date 9-16-98 RRC  
CALHOUN COUNTY  
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

|                                    |                         |               |
|------------------------------------|-------------------------|---------------|
| <u>CALHOUN</u><br>(County)         | Located In:             | Corner Code # |
| PENNFIELD TOWNSHIP                 | T <u>1S</u> R <u>7W</u> | <u>M-8</u>    |
| 1. Public Land Survey              | T _____ R _____         | _____         |
|                                    | T _____ R _____         | _____         |
|                                    | T _____ R _____         | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____         |
|                                    | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                    | S _____ T _____ R _____ | _____         |

25 SEP 1998 2:28:32 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2062** PAGE **587**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on AUGUST 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

### EAST 1/4 POST OF SECTION 24

#### A. Description of original monument and accessories and/or subsequent restoration:

SYLVESTER SIBLEY D.S. 1826, SET ORIGINAL CORNER  
J.M. GIFFORD 1891 RESURVEY, FOUND STUMP OF ONE GOVERNMENT BEARING TREE AND SET POST (TILE).  
WITNESS CARD, NO NAME OR DATE.

#### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG EXTENSIVELY AT AND AROUND MIDPOINT OF EAST SECTION LINE.

LOCATION IS NORTH OF EAST AND WEST ROAD, BUT IN AREA MOST LIKELY DISTURBED WITH ROAD BUILDING.

FINDING NO EVIDENCE OF CORNER OR WITNESSES REMAINING, SET BERNTSEN REMONUMENTATION MONUMENT AT MIDPOINT OF EAST LINE OF SECTION 24 WITH CARSONITE WITNESS POST BESIDE.

#### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704  
CENTERLINE OF EAST AND WEST ROAD IS SOUTHERLY 32 FEET, MORE OR LESS, AT 90° TO CENTERLINE.  
14" OAK, N05°W 10.20 FEET, SET SPOTTER  
8" OAK, N43°W 54.45 FEET, SET SPOTTER  
12" APPLE, N65°W 66.34 FEET, SET SPOTTER  
NORTHEAST CORNER OF POLE BARN, S05°E 218.44 FEET.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

Signed by [Signature]  
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998

