

APPROVED

Date 7-21-99 *rc*

CALHOUN COUNTY
REMONUMENTATION
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TOWNSHIP		
1. Public Land Survey	T <u>1S</u> R <u>7W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

27 JUL 1999 10:27:53 AM

ANNE S. NURLANDER
CLERK - REGISTER OF DEEDS

LIBER **2147** PAGE **716**
Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY SYLVESTER SIDLEY D.S., 1826
RESURVEY BY JAMES M. GIFFORD, 1891, FOUND CORNER KEPT BY JOSEPH MARKHAM
SINCE BEARING TREES WERE STANDING AND SET RESURVEY TILE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RESURVEY TILE (SOLID 3" TILE OVER HOLLOW TILE) REPLACED SOLID TILE WITH STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN CASTING.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNISEN MONUMENT IN CASTING.
N.W. CORNER OF STONE FOUNDATION OF CHURCH S 33°E, 135.16'
UTILITY POLE S 78°E 110.02' (NAIL AND SPOTTER)
24" OAK N 33°E 56.20' (NAIL AND SPOTTER)
36" OAK N 19°W 54.98" (NAIL AND SPOTTER)
30" OAK N 71°W 91.74' (NAIL AND SPOTTER)

THIS LOCATION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Robert R. Carr*

Date 7-21-99

Surveyor's Michigan License No. 20704 ROBERT R. CARR

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

