

# APPROVED

Date 7-21-99 RLC  
**CALHOUN COUNTY**  
**REMONUMENTATION**  
 For corners in

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

<u>CALHOUN</u> (County)	Located In:	Corner Code #
PENNFIELD TOWNSHIP	T <u>1S</u> R <u>7W</u>	<u>M-12</u>
1. Public Land Survey	T _____ R _____	<u>SURVEY &amp;</u>
	T _____ R _____	<u>REMONUMENTATION</u>
	T _____ R _____	<u>MAR 13 2000</u>
2. Property Controlling	S _____ T _____ R _____	<u>SECTION</u>
in Section	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	
Property in Sec.	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

27 JUL 1999 10:28:05 AM

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER 2147 PAGE 717  
 Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET SYLVESTER SIBLEY D.S. 1826  
 RESURVEY TILE SET BY JAMES M. GIFFORD IN 1891, CORNER LOST SET BY OCCUPATION.  
 SUBSEQUENT WITNESSES CARDS RECITE WITNESS FROM G.L.O. AND RESURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RESURVEY TILE SET BY JAMES M. GIFFORD IN 1891 AND REPLACED WITH STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX:  
 11" CHERRY N 39° W, 40.99' (NAIL AND SPOTTER)  
 36" OAK N 09° W, 103.65' (NAIL AND SPOTTER)  
 30" OAK S 14° W, 149.53' (NAIL AND SPOTTER)  
 UTILITY POLE S 85° W, 55.44' (NAIL AND SPOTTER)

THIS LOCATION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 7-21-99  
 Surveyor's Michigan License No. 20704 ROBERT R. CARR

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

