

APPROVED

Date 11/25/97 ARC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

1 DEC 97 4:50 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1980 PAGE 505

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u> (County)	Located in:	Corner Code #
BEDFORD TOWNSHIP	T <u>1S</u> R <u>8W</u>	<u>A-7</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on SEPTEMBER 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 SYLVESTER SIBLEY D.S. INTERSECTED WEST BOUNDARY 83 LKS
NORTH OF POST AND SET POST AT INTERSECTION FOR CORNER TO SECTIONS 18 & 19.
1888 SETH PRATT, RESURVEY, FOUND REMAINS OF STAKE ESTABLISHED
SETH PRATT 35 YEARS AGO, B.O. 18° N87-3/4°W 35 LKS; HICKORY 12" S6-1/4°W 61-1/2 LKS.
1978 L.C.R.C. BY MILTON E. DEKEYSER, IRON, 24" MAPLE, N75°E 88.16 FEET;
24" MAPLE, S50°W 31.72 FEET; U.P. N40°E 71.4 FEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON OVER TILE 54.54 FEET NORTH OF REMONUMENTED CORNER TO SECTIONS 13 & 24, T.1S., R.9W.
ALSO FOUND 6"x6"x2'-6" STONE ON END 1' ± NORTHEAST OF TILE.
RAN TOWN LINE FROM CORNER OF SECTIONS 13 & 24 NORTH TO WEST 1/4 POST, SECTION 13, T.1S., R.9W.
AND FOUND STONE TO BE ON LINE AND 54.78 FEET (83 LKS) NORTH OF ROSS TOWNSHIP CORNER.
ACCEPTED STONE AS TRUE PERPETUATION OF CORNER AND REPLACED WITH BERNTSEN MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX
SET SPOTTER IN UTILITY POLE, N69°E 45.97 FEET
SET SPOTTER IN 30" HICKORY, S11°E 105.54 FEET
SET SPOTTER IN 6" IRONWOOD, N78°W 26.57 FEET
SET SPOTTER IN 4" CHERRY, N27°W 46.12 FEET
9' ± NORTH OF CENTERLINE OF ROAD EAST
2' ± WEST OF CENTERLINE OF ROAD NORTH & SOUTH.

Signed by [Signature]
Surveyor's Michigan License No. 20704

Date 11/24/97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

