

FEB 2 2 1996

For corners in

5. Private Claims _

COMMISSION

CALHOUN COUNTY REMONUMENTATION

Date Nov. 20, 1995 CALHOUN COUNTY REMONUMENTATION.

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

4 DEC 95 2:23 P.N.

ANNE B. NORLANDER CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Calhoun Located In: Corner Code ≠ Bedford Township 1. Public Land Survey T 1 S R 8 W D-11 2. Property Controlling in Section 3. Miscellaneous Property in Sec.

__ , Recorded Plat _

1. William K. Crane , in a field survey on _ November 8 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned

in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

10 11 12

9.5'(stump)

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Field Notes (S. Sibley, 1826):	Re-survey, S. Pratt- 1888:	Clyde Chamber (no date):
12" B1. Oak N 33° E 14 links 9" B1. Oak S 07° E 17 links	12" B.O. N 33° E 14 links 12" Burr S 23° E 21½ links Oak	16" Elm NW 37.2' 24" B.O. Nly 9.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of witnesses or corner location. Area behind sewer treatment plant. There is evidence of dredging of stream running to Kalamazoo River. Set corner on line and halfway between C-11 and E-11. Distance from C-11 to E-11 is 5,310.86 feet.

LIRER 1834 PAGE 252

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set standard Calhoun County Remonumentation Corner (Bernsten Monument) at 1/2 way and on Section Line. Found remains of N-S fence 3' + West of proportional corner location.

15"	E1m			W	4.78
10"	Poplar	N	15°	W	23.20
	E1m	S	15°	W	12.37'
8"	E1m	S	20°	E	25.24

This is accepted as a careful and faithful re-establishment of the position of the original corner.

29243

Signed by Willam K. Crane Crane Surveyor's Michigan License No. _

__ Date <u>November 20</u>, 1995

NO. 29243 PROPERTY OF LAND SURVEYOR FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

CRANE SURVEYOR