

FEB 22 1996

COMMISSION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
Date Dec 18 1995
CALHOUN COUNTY
REMONUMENTATION.

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> S R <u>8</u> W	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

26 OCT 95 10:02 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

William K. Crane, in a field survey on October 16, 19 95,
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

Original Government Field Notes
(Sibley 1826):

6" W. Oak S58°W 871 links
8" W. Oak N89-3/4°W 1066 links

Resurvey S. Pratt (1888):

Found corner by measuring
West from corner Sections
4 and 5, Battle Creek,
153 links.

8" Popular N78-1/4°W 121 links
4" Popular S74-3/4°E 105 links

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found State of Michigan brass cap monument in 4" pipe with concrete, 100.98 feet West of
Battle Creek corner and below bolt as referred to in L.C.R.C. recorded in L. 1007, P. 81.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Bedford Township

Recorded by Milton
Dekeyser, L. 1007, P. 81.
Found 4" pipe with cap
8" below surface and
found bolt at surface.

LIBER 1828 PAGE 42

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left State of Michigan monument in place and set a monument box over it, 3'± South of
centerline bituminous road.

-10" Walnut N10°W 23.33'
-Concrete monument North 37.00'
-Utility pole S10°E 12.81'
-10" Elm N75°W 108.96'

This is accepted as the best available evidence of the
position of the original corner.

Signed by William K. Crane
William K. Crane
Surveyor's Michigan License No. 29243

Date October 18, 1995

