

1993

CALHOUN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

CALHOUN
 (County)

Located In:

Corner Code #

1. Public Land Survey	T 1S R 8W	K-10
	T _____ R _____	_____
BEDFORD TOWNSHIP	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK-REGISTER
 CALHOUN COUNTY, MICH.
 ANNE R. ANDERSON
 Oct 26 10 16 AM '93

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT R. CARR, in a field survey on AUGUST 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

RESURVEY
 U.S. BEARING & POST GONE
 ESTABLISHED BY LINING E.W.N. & S.
 BURR OAK 20" N72-3/4°W 166 LKS
 HICKORY 10" S49-1/2°E 118 LKS

McPHERSON 1971
 IRON
 U-POLE S30°W 51.35'
 U-POLE S55°E 67.35'
 U-POLE N40°E 72.45'
 10' W OF N/S CENTERLINE
 2.5' N OF E/W CENTERLINE

L.C.R.C. LIBER 1, PG. 112
 IRON
 U-POLE S30°W 51.35'
 U-POLE S55°E 67.35'
 U-POLE N40°E 72.45'
 10' WEST OF N/S CENTERLINE
 2.5' NORTH OF E/W CENTERLINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4 PIPE OVER 1-1/2" PIPE IN CONCRETE OVER TILE
 MATCHING WITNESSES FROM L.C.R.C. LIBER 1, PG 112.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NEAR CORNER OF 1.0' SQUARE M.B.T. RISOR N54°E 71.30'
 NAIL & SPOTTER IN NE SIDE 12" OAK N20°W 119.90'
 NAIL & SPOTTER IN NW SIDE GUY POLE 3.0' ABOVE GROUND S30°W 51.03'
 NAIL & SPOTTER IN SW SIDE 12" OAK S53°E 112.70'
 STANDARD CAL CO REMON MONUMENT WITH BRONZE CAP AND MONUMENT BOX OVER TILE

LIBER 1711 PAGE 099



Signed by Robert R. Carr Date OCT 20, 1993

Surveyor's Michigan License No. 20704