

SURVEY &
REMONUMENTATION

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNIE B. MORGAN ANDERSON

OCT 26 10 16 AM '93

RECORDED

For corners in

CALHOUN (County)	Located In:	Corner Code #
BEDFORD TOWNSHIP		
1. Public Land Survey	T 1S R 8W	K-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ROBERT R. CARR, in a field survey on SEPTEMBER 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11 RESURVEY: FD STAKE FROM SURVEY BY S. PRATT; U.S. BEARING GONE; 12" HICKORY N20°E, 56.8 FT., W.O. 24" S41-1/2°E, 83-1/2 LKS.; B.O. 7" N79-1/2°E, 26-1/3 LKS.
 D. DAVIS: NO DATE 5/8" IRON; 4 FT WEST OF CENTERLINE; IRON NORTH 28.88 FT.; 14" OAK N25°E, 25.38 FT.; 10" OAK N45°E, 29.70 FT.; ANGLE IRON EAST, 28.70 FT.; U-POLE N85°W, 17.13 FT.
 R. GERTZ 1972: STEEL PIN 4 FT. WEST OF CENTERLINE PAVEMENT; OVER BRICK; OVER TILE; SE CORNER BLDG NW, 121.7 FT.; FENCE EAST, 28.7 FT.; 14" OAK S60°E, 53.5 FT.; U-POLE N80°W, 17.5 FT; 15" OAK, N45°E, 30.0 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 FOUND IRON ROD & BRICK OVER TILE AS PER GERTZ, 1972.
THREE WITNESSES REMAINING.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 REPLACED IRON, BRICK & TILE WITH STANDARD CALHOUN COUNTY REMON MONUMENT WITH BRONZE CAP IN MONUMENT BOX. NAIL & SPOTTER IN SE SIDE OF 24" OAK, N35°E, 52.00 FT. CENTER OF TOP OF FIRE HYDRANT, N13°E, 179.75 FT. NAIL & SPOTTER IN EAST SIDE OF U-POLE, N01°W, 169.98 FT. SE CORNER BLDG FOUNDATION, N39°W, 127.67 FT. (NEW BLDG) 3.5 FT WEST OF CENTERLINE OF NORTH/SOUTH ROAD. IRON STAKE NORTH 28.29 FT.

LIBER 1711 PAGE 097



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date OCT 20, 1993