

SURVEY &
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANN F. B. NORTON ALDER

OCT 26 10 16 AM '93

RECORDED

For corners in **COMMISSION**

<u>CALHOUN</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>1S</u> R <u>8W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
BEDFORD TOWNSHIP	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, ROBERT R. CARR, in a field survey on AUGUST 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

RESURVEY
FOUND STONES & BRICK AS ESTABLISHED
BY S. PRATT FROM U.S. BEARING TREE
POPLAR 5" S19°E 39 LKS
B OAK 5" N52-1/4°E 46 LKS

DAVIS 1962
IRON STAKE OVER TILE
TWIN 10" CHERRY SOUTH 25.11'
36" OAK NNE 39.60'
GUY POLE NW 97.40'
TWIN 10" CHERRY S50°E 24.6'
TRIPPLE OAK N70°E 59.0'
4" B OAK NORTH 63.60'

DEKEYSER 1980
1" PIPE ON CENTERLINE ROAD
TWIN 12" CHERRY S05°E 24.90'
TWIN 12" OAK N50°E 89.50'
U-POLE N80°W 97.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE 3.3 FT BELOW SURFACE AND 1.2 FT WEST OF 3/4" IRON PIPE (DEKEYSER 1980).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED STANDARD CAL CO REMON MONUMENT WITH BRASS CAP IN MONUMENT BOX OVER TILE.
NAIL & SPOTTER IN ROOT ON S.E. SIDE OF TWIN OAK
12" & 16" N75°E, 59.13 FT.
CENTER OF 4" OAK S40°W, 52.10 FT.
NAIL & SPOTTER IN SW SIDE OF 10" OAK S37°E, 49.68'
NAIL & SPOTTER IN NW SIDE OF U-POLE 4.6 FT ABOVE GROUND S75°W 146.28 FT
1'± NORTH OF CENTERLINE PAVEMENT.

LIBER 1711 PAGE 098



Signed by [Signature] Date OCT 20, 1993

Surveyor's Michigan License No. 20704