

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

NOV 18 2 21 PM '93

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. NORLANDER

For corners in

CALHOUN COUNTY (County)	Located In:	Corner Code #
BEDFORD TOWNSHIP		
1. Public Land Survey	T <u>1</u> S R <u>8</u> W	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on OCTOBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>M-12 <u>RE-SURVEY</u> FOUND STAKE ESTABLISHED BY R.B. MERRITT. HICKORY 12" N8-1/2°W 166-1/2 LKS. 6" BLACK OAK WEST 12" BLACK OAK N80°W 310 LKS.</p>	<p><u>P. SALZGABER 1956</u> PIPE &amp; BRICK NW TOWER LEG S65°E 53.5 FT. HYDRANT N60°W 63.5 FT. U-POLE N40°E 54.8 FT. CENTERLINE PAVEMENT N &amp; S.</p>	<p><u>L.C.R.C. LIBER 1032, PG. 620</u> PIPE HYDRANT N60°W 63.5 FT. U-POLE N40°E 54.8 FT. CENTERLINE N &amp; S PAVEMENT.</p>
--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 FOUND 1" PIPE & BRICKS IN MONUMENT BOX OVER TILE OVER HOLLOW CONCRETE MONUMENT MATCHING WITNESS FROM L.C.R.C. LIBER 1032, PG. 620.  
REPLACED PIPE, BRICK & TILE WITH STANDARD CALHOUN COUNTY REMON MONUMENT.

LIBER 1716 PAGE 441

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 STANDARD CALHOUN COUNTY REMON MONUMENT WITH BRONZE CAP IN MONUMENT BOX.  
SET NAIL AND SPOTTER IN SOUTH SIDE OF 16" OAK S80°E 51.14 FT.  
SET NAIL AND SPOTTER IN SE SIDE OF 15" HICKORY N25°E 114.10 FT.  
EAST RIM MANHOLE N85°W 24.13 FT.  
TOP NUT FIRE HYDRANT N60°W 63.19 FT.  
NW LEG OF C.P. CO. TOWER S63°E 53.80 FT.



Signed by Robert R. Carr  
Surveyor's Michigan License No. 20704

Date NOVEMBER 17, 1993