

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
Date Oct. 18 1995
CALHOUN COUNTY
REMONUMENTATION.

For corners in
Calhoun

	Located In:	Corner Code #
Sheridan Twp.		
1. Public Land Survey	T <u>2</u> S R <u>4</u> W	G-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

26 OCT 95 10:14 A.M.

Register of Deeds Stamp & File Number

ANNE D. HORLANDER

CLERK - REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald J. Davis, in a field survey on August 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Lyon.
18" Burr Oak S 55° W 77 links, 9" White Oak N 26° E 45 links.
Bolt set in bituminous road by M.D.S.H. in 1959.
30" Oak N 29° W, 35.20'.
16" Cherry N 34° E 45.34'.
Concrete post S 87° E 28.20'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bolt in bituminous surface.
Dug and found 1" pipe 1 foot below surface.

Accepted as good location of corner.

LIBER 1828 PAGE 65

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box at point.
Centerline of bituminous road.
Nail & Tag 24" Cherry N 35° E 45.45'
Nail & Tag Utility pole N 30° E 91.10'
Nail & Tag 38" Burr Oak N 35° W 35.18'
Nail & Tag utility pole S 25° E 80.50'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date September 29, 1995