

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date 8/16/95
CALHOUN COUNTY
REMONUMENTATION.

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>4W</u>	<u>G- 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

30 AUG 95 11:28 A.M.

ANNE B. NORLANDER
 Register of Deeds

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald J Davis, in a field survey on August 9, 1995, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original survey in 1825 by Lyon 18" oak N58W 80 lks 14" W oak S22E 291ks
 Corner reset in 1932 and used in survey.
 Corner reset in 1962 by J Alden for plat recorded in Liber 16 of plats on page 39 from Barry notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Corner was destroyed during street construction for plat.
 Reset corner from plat information. Excavated and found large rock 1 1/4 feet under road.
 Set corner over rock.

Accepted the location as shown on plat as acceptable for corner.

REMONUMENTATION

LIBER 1818 PAGE 321

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set harrison monument in monument box at corner location.

- 56 feet south of the intersection of streets in plat.
- nail & tag Utility Pole N70E 40.47 feet.
- " " 18 " Twin Cherry N40W 169.50 feet.
- " " Utility Pole East 112.10 feet.
- NW corner of building foundation S30E 158.35 feet.



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date August 17, 1995