

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date 8/11/95 *LDJ*
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in
Calhoun
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>2S</u> R <u>4W</u> | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

30 AUG 95 11:28 A.M.

ANNE B. NORLANDER
Register of Deeds Stamp & File Number
CLERK REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald J. Davis
I, _____, in a field survey on August 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey in 1825 by Lyon.
- 10" White Oak East 60 links, 15" Burr Oak N 5° W 48 links.
- 1" iron pipe in 1938 by R.L. Barry, RLS #2258.
- 16" White Oak NW 5 1/2".
- RR iron post SW 3.70'.
- 1" iron pipe (recorded Liber 1006, page 664), David Greer.
- 30" Oak East 11.24', Power pole NW 63.00'
- 24" Oak NW 0.32'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in base of 30" White Oak, checked to witnesses of Greer.
Accepted as good location of corner.

CALHOUN COUNTY
REMONUMENTATION

LIBER **1818** PAGE **324**

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" iron with cap in 1" pipe in south edge 30" Oak.
- Nail & Tag 48" White Oak East 11.45'.
- Nail & Tag Utility pole N 45° W, 63.00'.
- Nail & Tag 12" Red Oak South 30.90'.
- NE leg of Consumers Power tower S 85° W 104.16'.
- RR rail post S 45° W 3.40'.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 11, 1995