

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date 8/14/95
 CALHOUN COUNTY
 REMONUMENTATION

For corners in
Calhoun
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>4W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 30 AUG 95 11:27 A.M.
 ANNE B. NORLANDER
 Register of Deeds State of Michigan

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Donald J Davis, in a field survey on August 10, 1995, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original survey in 1825 by Lyon 10" WOak N80E 70lks, 14" W Oak N72W 38 lks
 Corner reset in 1940 by AH Chase 35 feet east of the North 1/4 post section 3 T3S, R4W.
 Concrete Monument set in 1962 by DeKeyser
 NE corner conc scale foundation West 76.34
 3.5 feet north of old chain link fence.
 Corner used by Consumers Power Co in survey in 1979.
 35 feet east of Albion corner as marked by 3/4" pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Concrete monument from oldnotes and matches distance to adjacent Albion corner
 Accepted as a good location of the corner perpetuation.

CORNER & REMONUMENTATION

LIBER 1818 PAGE 316

FEB 22 1996
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Concrete Monument with cap.
 Nail and Tag 16" ash West 2.25 feet
 " " : 14" ash N10 E 26.61 feet
 " " " 6" cherry N45 W 10.21 Feet
 " " " 14" oak East 29.30 feet.
 3.5 feet north of old chain link fence
 35 feet east of North 1/4 post section 3 Albion Twp.



Signed by Donald J Davis
 Surveyor's Michigan License No. 17617

Date August 11, 1995