

APPROVED

Date 11/17/99 REC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

17 DEC 1999 2:27:29 PM

For corners in Sheridan Township

<u>CALHOUN</u>	Located In:	Corner
Code #		
(County)		
1. Public Land Survey	T <u>2S</u> R <u>4W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2185** PAGE **982**

Register of Deeds Stamp & File Number

I, MICHAEL P. PRATT, in a field survey on NOVEMBER 6, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. in 1825 by Lucius Lyon.
10" B.O., S.61°W., 60 lks;
7" W.O., N.01°E., 73 lks

F.A. Courtright, C.S. in 1893 - found Iron and remains of one GLO witness.

Witness card of Crane Land Surveying and Carr & Associates: 1" Iron rod, 1.8' East of centerline.
36" W. Oak, N.85°W., 31.33'
32" R. Oak, East, 29.52'
36" Elm, N.45°E., 45.2'

S. Smith in 1974: 5/8" Iron Bar in Mon. Box
44" Oak, N.80°W., 30.3'
36" Oak, East, 29.17'
32" Apple, S.45°E., 48.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 18" iron rod in monument box. Excavated 18" in monument box and found large stone (whole width of box) with no particular markings. Accepted the location of the iron and stone as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument in monument box

Witnesses:

- Found nail & tag in 42" Oak, S.84°E., 29.80'
- Set nail & CCRC tag in 12" Triple Cherry, N.29°E., 69.50'
- Found nail in 54" Twin Oak, N.70°W., 31.30'
- Set nail & CCRC tag in 14" Twin Elm, S.26°W., 111.20'
- In centerline of N-S road and 5' South of fence west..

Signed by

Michael P. Pratt

Michael P. Pratt, P.S.

Date

12/18/99

Surveyor's Michigan License No. 43067

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

