

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**APPROVED**  
 Date Sept. 28 1995  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

22 SEP 95 10:00 A.M.

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Calhoun

(County)

Sheridan Twp.

Located In:

Corner Code #

- |                                       |                           |             |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey                 | T <u>2</u> S R <u>4</u> W | <u>I-12</u> |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                           |             |
| 5. Private Claims _____               |                           |             |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald J. Davis, in a field survey on August 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1825 by Lyon (no witnesses).  
 Chiseled "X" in concrete paving by Barry, RLS, in 1938.  
 Centerline North Street to East.  
 SE corner house #1001 NW 64.00'  
 NE corner house #927 SW 87.25'

LIBER **1822** PAGE **27**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated thru 4" bituminous paving at point set from Barry witnesses. Found no evidence of "X" as concrete paving was in poor condition.  
 Found no evidence under concrete paving.  
 Accepted point as good location for restoring corner.

COMMISSION  
 REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.  
 SE corner of house #1001 N 80° W 64.00'  
 NE corner of house #927 S 68° W 87.25'  
 NW corner house foundation S 45° E 98.60'  
 SW corner brick office building N 50° E 70.58'



Signed by Donald J. Davis  
 Surveyor's Michigan License No. 17617

Date September 15, 1995