

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date 8/16/95 *WJD*
CALHOUN COUNTY
REMONUMENTATION.

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>2</u> S R <u>4</u> W	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 30 AUG 95 11:27 A.M.
 ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald J. Davis, in a field survey on August 2, 1995,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**


Description of original monument and accessories and/or subsequent restoration:
 Original survey in 1825 by Lyon.
 8" White Oak N 69° E, 82 links.
 36" White Oak N 26½° W, 90 links.
 ½" copper rod in 8" pipe in concrete paving, 1938, R.L. Barry, RLS #2258
 NW Corner Gas Co. Bldg, S 82° E, 96.80'
 SE corner Coal Co. office N 45° W, 57.45'.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found ½" copper rod in concrete in monument box which checks to above witnesses by Barry.
 Accepted corner as good location of corner perpetuation.

CORNER
 REMONUMENTATION
 FEB 22 1996
 COMMISSION

LIBER 1818 PAGE 319

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 8" Brass rod in concrete in monument box in Eaton Street.
 NW corner Gas Co. brick bldg. S 82° E 96.80'.
 SE corner concrete foundation Coal Co. office N 45° W, 57.45'.
 Nail & Tag Utility pole S 45° W, 50.28'.
 Nail & Tag Utility pole S 20° W, 136.27'.
 Nail & Tag Utility pole N 20° W, 97.46'.



Signed by Donald J. Davis Date August 11, 1995
 Surveyor's Michigan License No. 17617