

MAR 13 2000

APPROVED

Date 11/17/99 rec
CALHOUN COUNTY
REMONUMENTATION.

SECTION
CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in Sheridan Township

17 DEC 1999 2:26:40 PM

<u>CALHOUN</u>	Located In:	Corner
Code # (County)		
1. Public Land Survey	T <u>2S</u> R <u>4W</u>	<u>J-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2185** PAGE **978**
Register of Deeds Stamp & File
Number

I, MICHAEL P. PRATT, in a field survey on NOVEMBER 6, 19 99
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
points mentioned in lines 1 and 2 above were in conformance with regulations and rules
therefore as required in the current manual of survey instructions of the United States
Department of the Interior, Bureau of Land Management or by a decree of a Court of Law
and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance
with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;
established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may
be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent
restoration:

G.L.O. in 1825 by Lucius Lyon. 8" W.O., S.89°E., 5.80lks;
9" B.O., N.63°W, 1.81 lks
Carroll Pike in 1974, 3/4" Iron pipe
18" Oak, N.70°W., 81.20'
R.R. tie fence post, North 22.29'
5' North of centerline of E-W road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" x 18" iron pipe: Excavated 3' below surface of road and did not find any other monumentation.
Accepted the location of the iron pipe as the pipe described by C. Pike and the best available evidence of the position
of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box

Witnesses:

Found nail in 24" Twin Oak, N.70°W., 63.40'
Found nail in R.R. tie fence post, North, 21.8' (22.29' at base)
Found nail in U.P., S.45°E., 45.22'
Found nail & tag in U.P., S.74°W., 80.00'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	10			17		16			15		14		13
7													
8	19			20		21			22		23		24
9											26		25
10	30			29		28			27				
11													
12	31			32		33			34		35		36
13													



Signed by [Signature]

Date 12/8/99

Michael P. Pratt, P.S.

Surveyor's Michigan License No. 43067