

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

Calhoun
Sheridan Twp.

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------------------------|-------------|
| 1. Public Land Survey | T <u>2</u> S <u>4</u> R <u>W</u> | <u>J-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

22 SEP 95 10:00 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1825 by Lyon.
6" Burr Oak N 45° E 72 links.
15" Burr Oak N 48½° W 139 links.
No record of corner found or used.

All plats in City of Albion referenced to each other and none to corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set point on line at midpoint between SE and SW corner of section.
Excavated in centerline of Michigan Avenue and found no evidence of corner.
Accepted midpoint as location of restoring corner point.

CORNER
REMONUMENTATION

LIBER 1822 PAGE 29

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box, falls on centerline of Michigan Avenue.
NE corner of house foundation S 30° W 70.46'
NW corner house foundation, #512, S 15° E 83.25'
Face of east 6" steel gate post N 45° W 71.85'
Nail & Tag light pole N 45° E 56.17'



Signed by Donald J. Davis Date September 15, 1995
Surveyor's Michigan License No. 17617 Donald J. Davis