

MAR 30 1999

SECTION

APPROVED

Date 12-9-98 *RRC*
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u>	Located in:	Corner Code #
(County)		
SHERIDAN TOWNSHIP		
1. Public Land Survey	<u>T 2S R 4W</u>	<u>K-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

15 DEC 1998 3:36:32 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **930**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael A. Groat, in a field survey on December 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, 1825, SET POST 40 CHS NORTH OF SE COR, SECTION 12, W. OAK, 11", S 89° E, 70 LKS, W. OAK 7" N 45° E, 1.2 LKS.
1976, T.P.J., SET R.R. SPIKE MIDWAY ON LINE BETWEEN CORNERS; 8" W. OAK, N 40° E, 64.7'; 24" OAK, WEST 30.2'; 14" R. OAK, S 35° E, 78.5'; 6' WEST OF CENTERLINE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND R.R. SPIKE CALLED FOR BY T.P.J. ABOVE. THE CORNER FALLS ON THE DOWN SIDE OF A HILL IN THE ROAD AND NO EVIDENCE OF THE ORIGINAL CORNER WAS FOUND. TRAVERSED TO THE CORNERS NORTH AND SOUTH AND VERIFIED THAT IT WAS MID-WAY ON LINE. ACCEPTED THE LOCATION OF THE R.R. SPIKE AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN MONUMENT BOX IN PLACE OF R.R. SPIKE.
NAIL & TAG IN 24" OAK, N 84° W, 30.30'
NAIL & TAG IN 12" CHERRY, S 80° E, 31.72'
NAIL & TAG IN 24" CHERRY, N 50° E, 49.42'
NAIL & TAG IN 15" OAK, S 40° W, 36.84'



Signed by Michael A. Groat
Surveyor's Michigan License No. 39079

Date December 6, 1998