

MAR 13 2000

**APPROVED**

SECTION

Date 11/17/99 *ERC*  
CALHOUN COUNTY  
RECORDATION

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in Sheridan Township

Code #	<u>CALHOUN</u> (County)	Located in:	Corner
1. Public Land Survey	T <u>2S</u> R <u>4W</u>		<u>K-9</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

17 DEC 1999 2:26:15 PM  
WINE D. NORLANDER  
CLERK - REGISTER OF DEEDS  
**LIBER 2185 PAGE 977**  
Register of Deeds Stamp & File Number

I, MICHAEL P. PRATT, in a field survey on September 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. in 1825 by Lucius Lyon. 22" W.O., S.74°W., 76 lks;  
20" W.O., N.74°E, 52 lks;

Witness card dated 1976 (no name), 3/4" pipe at West edge.  
MBT pole, S.40°E., 44.0'; MBT pole, S.75°W., 88.0'; U.P., N.33°E., 75.8'

Witness card (no name or date), 3/4" pipe, 33 feet West of east road fence.  
24" Hickory, N.10°W., 148.7'; 24" Maple, S.70°E., 111.2'

Don Davis in 1976, Found 3/4" pipe in west edge of pavement, centerline of road N-S.  
MBT pole, S.40°E., 44.0'; MBT pole, S.75°W., 88.0'; U.P., N.33°E., 75.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x 0.4' iron pipe at surface of road. Dug to 1.2' and found 1"x24" solid iron rod 0.05' East of pipe and bent 0.15' to the North. Excavated to 3' below surface of road and did not find any other monumentation. Accepted the location of the iron pipe as the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box

Witnesses:

- Found nail in U.P., S.37°30'E., 44.00'
- Set nail & CCRC tag in U.P., N.34°E., 76.25'
- Found nail & tag #25332 in U.P., North 01°30' West, 75.20'
- Stop sign, S.66°W., 33.95'
- 12' West of centerline of N-S road, 1' North of centerline of E-W road.



Signed by *Michael P. Pratt*  
Michael P. Pratt, P.S.

Date 12/8/99

Surveyor's Michigan License No. 43067