

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date 8/11/95 *DJD*
CALHOUN COUNTY
REMONUMENTATION.

For corners in
Calhoun
 (County)

Located In: Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>2</u> S <u>4</u> W | <u>K-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

30 AUG 95 11:27 A.M.

ANNE B. NORLANDER
 Register of Deeds Stamp # _____

Donald J. Davis in a field survey on July 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1825 by Lyon, NO WITNESSES REMAIN.
 16" White Oak N 10° E 14 links, 16" White Oak S 37° E 51 links.
 Corner monument set by Barry in 1938 for Plat. Corner used by M.D.S.H. in 1959.
 14" Red Oak N 30° E 50.55' R.L. Barry, RLS #2258
 10" Red Oak S 78° E 46.45'
 Concrete corner post West 34.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron over 4" x 4" x 4" concrete monument set by Barry in 1938.
 Accepted as good perpetuation of location of corner.

CERTIFICATE
 REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1818 PAGE 318

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with box in bituminous road.
 Nail & Tag 10" Hickory S 40° E 55.88'
 SW corner garage foundation N 70° E 85.11'
 Nail & Tag utility pole N 80° E 22.41'
 NE corner house.



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date August 11, 1995