

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date 8/14/95
CALHOUN COUNTY
REMONUMENTATION.

For corners in
Calhoun
 (County)

Located In: Corner Code --#

1. Public Land Survey	T <u>2</u> S <u>4</u> R <u>W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

30 AUG 95 11:27 A.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Donald J. Davis, in a field survey on July 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1825 by Lyon.
 28" White Oak N 35° E 136 links.
 18" White Oak S 18½° W 33 links. NONE REMAIN

Monument set in 1938 by Barry for Plat, Liber 9A, page 10. R.L. Barry, RLS #2258.
 ½" pipe in monument box by M.D.S.H. in 1959.
 14" Red Oak S 81° W 44.57'
 27" Red Oak N 22° W 53.10'
 RR iron corner post S 60° E 34.62'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ¾" pipe in monument box as set by M.D.S.H. in 1959.
 Accepted as good perpetuation of location of corner.

CANCELLED
 REMONUMENTATION
 FEB 22 1996
 COMMISSION

LIBER 1818 PAGE 317

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.
 Nail & Tag Utility pole N 80° E 34.88'
 Nail & Tag light & guy pole S 40° W 41.80'
 Nail & Tag Utility pole N 60° W 40.92'
 NW corner block bldg S 50° E 58.80'



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date August 11, 1995