

**SURVEY &  
REMONUMENTATION**

MAR 13 2000

**APPROVED**

**SECTION**

Date 11/17/99 *RRC*  
**CALHOUN COUNTY**  
REMONUMENTATION.

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

17 DEC 1999 2:25:52 PM

For corners in Sheridan Township

<u>CALHOUN</u>	Located In:	Corner
Code # (County)		
1. Public Land Survey	T <u>2S</u> R <u>4W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____; Recorded Plat _____		
5. Private Claims _____		

WHEE B. NORLANDER  
CLERK - REGISTER OF DEEDS  
**LIBER 2185 PAGE 975**  
  
Register of Deeds Stamp & File  
Number

I, MICHAEL P. PRATT, in a field survey on September 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													25
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. in 1825 by Lucius Lyon. 8" R.O., S.03°W., 2.27 lks;  
5" W.O., N.80°W, 1.22 lks;

F.A. Courtright, C.S. - Found remains of one G.L.O. witness and stake set bt W.W. Gifford - no witnesses.

Roy F. Barry in 1937 - Point over culvert. 7" Y. Oak, S.11°W., 444 feet; 7" Y. Oak, S.76-1/2°W., 131 3/4 feet.

Witness Card - 1976 (no name) - U.P., S.11°W., 29.25'; 15" Oak, N.69°W., 60.4'; Top of R.R. Rail, N.10°E., 29.15'

Don Davis in 1976 - U.P., S.11°W., 29.25'; 15" Oak, N.69°W., 60.4'; Top of R.R. Rail, N.10°E., 29.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found newer 1/2"x 18" rebar matching witnesses of Davis. Excavated to 3' below surface of road and did not find any other monumentation. Accepted the location of the rebar as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box

Witnesses:

- Found nail in U.P., S.10°W., 29.6'
- Set Nail & tag in 18" Oak, N.70°W., 60.35'
- Top of railroad rail post, N.10°E., 25.0'
- Found nail in 18" Twin Oak, S.83°W., 123.85'



Signed by *Michael P. Pratt*

Date 12/8/99

Michael P. Pratt, P.S.

Surveyor's Michigan License No. 43067