

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
Date Nov 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**
STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED
4 DEC 95 2:30 P.M.
ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

For corners in Calhoun (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>2S</u> R <u>5W</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Marengo

I, Michael A. Groat, in a field survey on May 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Lyon	Gifford, 1890
6 Links South of Marshall corner	8" Maple, N 8°W, 196 Links
12" White Oak, S 76°E, 7 Lks	8" Hickory, S 11°West, 265 Links
10" White Oak, N 33°E 32 Lks	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron 6 Links South of Marshall Corner. No witnesses remain. Talked with local surveyors and this corner had been used in the past on private surveys. Dug but found no remains of tile. Accepted as a good perpetuation of the original corner.

REMONUMENTATION
FEB 22 1996
COMMISSION

LIBER 1834 PAGE 266

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a Harrison monument, from which:
Steel fence post, N 80°E, 27.00'
Nail and spotter in U.P., N 40°E, 78.40'
Nail and spotter in 12" Apple, S 23°W, 93.6'
Nail and spotter in 6" Apple, N 9°E, 145.2'



Signed by Michael A. Groat *Michael A. Groat* Date 11-18-95
Surveyor's Michigan License No. 39079