

REMONUMENTATION

MAR 21 1997

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 96 2:02 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 623

Register of Deeds Stamp & File Number

APPROVED

Date 11-12-96 *10810*

CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u>	Located in:	Corner Code #
(County)		
MARENGO TOWNSHIP		
1. Public Land Survey	T <u>2S</u> R <u>5W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on NOVEMBER 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR IN 1825, SET POST; W. OAK, 10° S 86° W, 30 LINKS

RE-SURVEY BY JAMES GIFFORD, 1890, FOUND ONE GOVERNMENT BEARING TREE AND STAKE, SET POST; W. OAK, 26°, S 86° W, 29 LINKS, Y. OAK, 13°, N 23° W, 7 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO RECENT INFORMATION COULD BE FOUND ON THIS CORNER. EXCAVATED A 6x6x3' HOLE AT OCCUPATION. THERE IS A FENCE LINE LYING DOWN RUNNING NORTH, SOUTH AND WEST. A ROCK WALL ALSO RUNS TO THE WEST. FOUND REMAINS OF OLD 1' DIAMETER FENCE CORNER BURIED IN THE GROUND. TRAVERSED FROM THE NORTHEAST SECTION CORNER TO THE SOUTHEAST SECTION CORNER AND SET A POINT MID-WAY ON LINE BETWEEN THE TWO. THIS POINT FALLS 1.5 FEET EAST OF THE OLD FENCE CORNER AND IS GOOD NORTH AND SOUTH. ACCEPTED THE POSITION OF THE POINT MID-WAY ON LINE AS THE BEST PERPETUATION OF THE ORIGINAL CORNER.

THE MILE MEASURED 5289.70 FEET AND THE CORNER WAS SET AT 2644.85 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT WITH SECTION INFORMATION AND P.S.#39079 STAMPED IN THE BRASS CAP. PLACED A CARSONITE MARKER BESIDE.

WITNESSES:
3 FEET EAST OF OLD FENCE NORTH AND SOUTH
1 FOOT SOUTH OF ROCK WALL AND FENCE WEST
SOUTH, NAIL AND SPOTTER IN WEST SIDE OF A 8" ASH, 4.95 FEET
193° NAZ, NAIL AND SPOTTER IN WESTERLY SIDE OF A 24" CHERRY, 40.95 FEET
284° NAZ, NAIL AND SPOTTER IN SOUTHERLY SIDE OF A 8" ASH, 38.23 FEET
355° NAZ, NAIL AND SPOTTER IN EAST SIDE OF A 24" OAK, 56.32 FEET

NAZ = AZIMUTH MEASURED FROM MAGNETIC NORTH

Signed by Michael A. Groat

Date NOVEMBER 12, 1996

Surveyor's Michigan License No. 39079

